FY 2012 - 2021 STATEWIDE TRANSPORTATION IMPROVEMENT PROGRAM
New Jersey Department of Transportation

Route 45, Carpenter Street to Red Bank Avenue

DB #   05310   UPC   053100   MILEPOST(S): 25.50 - 26.30

COUNTY: Gloucester   MUNICIPALITY: Woodbury City

This section of Rt. 45 from Carpenter St. to Red Bank Ave. in the City of Woodbury, Gloucester County will be converted from two lanes in each direction to a new cross section, consisting of one lane in each direction, a center turn lane, with a bike lane and parking on the outside where practical.

ASSET MANAGEMENT CATEGORY: Congestion Relief-Highway Operational Improvements   LEGISLATIVE DISTRICT: 5

AIR QUALITY CODE (NON-EXEMPT/EXEMPT):   2020M (Non-Exempt)

FINANCIAL PLAN REQUIREMENT:

SPONSOR: NJDOT   STRUCTURE NO.:   N/A

MPO	Phase	Fund	Amounts in Millions of Dollars									
			FY 2012	FY 2013	FY 2014	FY 2015	FY 2016	FY 2017	FY 2018	FY 2019	FY 2020	FY 2021
DVRPC	CON	NHS	$2.100									

Route 45, Gloucester County Drainage

DB # 09696   UPC   096960   MILEPOST(S): 28.4

COUNTY: Gloucester   MUNICIPALITY: Westville Boro

NJ Route 45 MP 28.4 floods during moderate rainfall events. The flooding at this location is caused by a collapsed 54-inch CMP culvert under the embankment of US Route 130 Northbound Ramp. The proposed improvements includes construction of a 54″ reinforced concrete pipe (RCP) under Route 130 NB Ramp near the collapsed 54″ CMP to restore capacity of the existing drainage system, and upgrading of existing 18″ RCP pipes along NJ Route 45 SB to 24″ RCP pipes.

ASSET MANAGEMENT CATEGORY: Road Assets-Drainage   LEGISLATIVE DISTRICT: 5

AIR QUALITY CODE (NON-EXEMPT/EXEMPT): S2 (Exempt)

FINANCIAL PLAN REQUIREMENT:

SPONSOR: NJDOT   STRUCTURE NO.:

			Amounts in Millions of Dollars									
MPO	Phase	Fund	FY 2012	FY 2013	FY 2014	FY 2015	FY 2016	FY 2017	FY 2018	FY 2019	FY 2020	FY 2021
DVRPC	CON	NHS	$1.400									