Pulaski Skyway Corridor Rehabilitation Program








Corridor Definition



- Pulaski Skyway Viaduct
- East Approach
- Pulaski Skyway is 3 ½ miles long
- Direct Link to Holland Tunnel via Route 139
- Links Newark at Raymond Blvd. & Jersey City at Tonnele Ave Circle
- Broadway Ramp southbound entrance, northbound exit to Jersey City
- Kearny Ramp southbound exit, northbound entrance to Kearny






Superstructure



Main Thru-Truss



Deck Truss



Multi-Girder Spans



Thru-Truss (Span 20)



Thru-Truss (Span 44)



Substructure

Concrete Encased Piers





Reinforced Concrete Piers



Substructure



Steel Bent Pier

Steel Columns and Cross Frames





Existing Conditions Superstructure





Vehicular Impact to Diagonal Member



100% Loss to South Truss Lacing Bars and Horizontal Legs of Bottom Angles

Holed-Through Gusset Plate in Lower Chord



Existing Condition Superstructure



Section Loss and Holes on Hanger



Up to 50% Section Loss Hanger Vertical Members



Up to 100% Section Loss Floorbeam Member



Existing Conditions Superstructure & Deck Components






Holes in adjacent web panels

Hole in stringer with entire end panel missing



Existing Condition Substructure



Reinforced Concrete Abutments

- Exposed and Rusted Reinforcing Steel
- Concrete Delamination
- Random Medium to Wide Cracks



Exposed Bottom Flanges of Pier Caps Exhibit Moderate Corrosion and Efflorescence



Existing Condition Substructure

Reinforced Concrete Piers

- Chipped and Split Concrete With Exposed Reinforcing Steel
- Areas of Delamination
- Vertical and Horizontal Cracks From 1/8 Inch to 1/4 Inch Wide







Existing Condition Substructure



Cracked Weld at Column / Pier Cap
Connection



Up to 50% Anchor Bolt Section Loss at Base of Column for Pier Bent



Underlying Deck Condition

Examples of severely deteriorated, cracked and patched concrete deck







Interim Rehab/Repair Contracts


\$90M in interim construction projects:

- No. 1 Deck repairs Spans A0 to 44 Complete- \$22M
- ➤No. 2 Deck repairs Spans 45 to 108 & overlay entire deck Complete \$23M
- ➤No 3. Priority repairs from inspection report Complete \$6M
- ➤ No 4. Drainage protection repairs Nearing Completion- \$38M



Existing Traffic Flows

- Carries 67,000 vehicles per day
- Carries 3,500 NB/2,640 SB in AM peak hour
- Carries 3,035 SB/2,905 NB in PM peak hour





ALTERNATIVE ANALYSIS




Task Force Started the Assessment Process

- Task Force charged with developing a comprehensive plan to address the needs of this complex structure
- Members included representatives from NJDOT, FHWA, SHPO, NJ TPK, PANYNJ, NJDEP, NJ Transit, TRANSCOM
- First Task Force meeting held 11/2005
- Discussions during this collaborate effort formed the basis of the Concept Development alternatives.



2008 Concept Development Public Involvement Program



- Local Officials and Agency Meeting
- Public Info Center
- Newsletters
- NJDOT website
- Fact Sheet
- Library Program
- Stakeholder databases



Local Officials & Agencies Meeting

Invitees:

- > Essex and Hudson Counties
- > Hudson TMA
- > Newark
- Jersey City
- > Kearny
- > Meadowlink
- > TRANSCOM
- > SHPO
- > NJTPA
- > NJTPK
- > PANYNJ





Alternatives Considered

- No Build Bridge Closed and Removed No Provision for Displaced Traffic
- No Build Bridge Closed and Removed -Provide Alternate Route Improvements
- New Parallel Structure and Rehab Existing
- New Parallel Structure and Demolish Existing
- Rehabilitate Skyway
 - > Rehabilitate and Widen Skyway
 - > Rehabilitate and Relocate Center Ramps to Outside
 - Rehabilitate Skyway in Current Configuration (PPA)



Preliminary Preferred Alternative (PPA)

Rehabilitate Structure in Current Configuration

- Selected based on:
 - Ability to roll-out Safety Improvements sooner
 - > Improved Quality of final product
 - > ROW cost is relatively low
 - ➤ Lowest Construction Cost (\$1B)
 - > Minimal environmental impacts
- Design for 75 year service life





DECK CONSTRUCTION STAGING ALTERNATIVES



Deck Replacement Alternatives Studied

Overnight/Weekend Construction

- Maintain peak period capacity
- Night and Weekends Construction closes one bound
- Estimated Construction Cost \$571M
- Construction Duration over 6 years

Close 1 Bound Full Time

- Either NB or SB direction closed
- Options to maintain traffic on open bound
- Estimated Construction Cost \$355M

Construction Duration Approximately 24 months

SB

Either Bound could be closed


Close 1 Bound Preferred Due to Quality, Safety, Duration & Costs

- Construction Costs Savings \$216M
- Construction Duration Savings at least 4.5 years



Close 1 Direction Alternatives Analyzed


- Northbound direction full time closure
 - > Better facilitation of evacuation of Jersey City & NYC
 - More choices for NB traffic prior to closure point
- Southbound direction full time closure
 - Concern of backups thru Tunnel into NYC
 - Concern of impeding access to Newark Airport
 - Compounds conflict with Turnpike WB construction (1-lane reduction) resulting in additional impacts to Jersey City streets
- Close 1 bound and maintain 1 lane in each direction
 - Not enough width to safely provide 1 lane in each direction
- Close 1 bound w/Peak Period reversible lanes
 - Operational concerns and costs of moving barriers twice a day, safety related to motorist expectations
 - Difficult ramp access
 - Loss of all capacity during switching periods: would mean significant detouring of traffic into and through Jersey City and Newark during off-peak periods






Closing the Northbound Direction

Pulaski Contract 3




Pulaski Contract 4



- Maintain SB direction of traffic leaving Jersey City & NY
 - Northbound Traffic Impacts approximately 24 Months starting in March 2014.
 - Completed before Route 7 Roadway Construction for the Wittpenn Bridge Replacement begins.



Weekday Morning Origin & Destinations






Traffic Mitigation Concepts

- Coordinate Pulaski Deck Construction with other Regional Construction Projects:
 - Pulaski Contract 2: East Approach (Route 139) Improvements
 - Wittpenn Bridge (Route 7)
 - ➤ NJ Turnpike Newark Bay Hudson County Extension (I-78/NB-HCE)
- Transit and TDM measures estimated to result in 5% to 10% peak hour trip reductions.
- Optimize network to favor NB flow on other facilities including 1&9T. – ONGOING ANALYSIS
- Use NB Shoulder on I-78/NB-HCE as Travel Lane.




2014 and 2015 Regional Projects







Expected Roadway Diversions





Roadway Capacity Mitigation Strategies





Route 1&9 Truck NB Optimization

- Signal Optimization and Adaptive Signal Control
- Geometric/Striping Improvements at Hackensack Avenue and Newark Avenue
- Phasing Improvements at Newark Avenue
- Proposing Removing Left Turn phase at Duncan Avenue
- Additional Ramp Lane from 1&9 Local to 1&9 Truck creating a Two-Lane Ramp



TRANSPORTATION MANAGEMENT PLAN



Transportation Management Plan (TMP)

- Comprehensive planning effort to minimize traffic impacts to the region.
- Coordination among other regional agencies with planned projects.
- Examining ways to increase capacity on diversionary routes.
- Examining methods to increase transit services/options.
- User survey has gathered information on traveler's alternate route/mode preference during lane closures.
- Task Force has been developed consisting of Locals and regional agencies to develop and implement the TMP



TMP Subcommittees Formed

- Incident Management
- Travel Demand Management (TDM) and Transit
- Traffic Control and Operations
- ITS Management
- Construction and Contracting
- Public Information



January/February 2013 Coordination Meetings

- Fifteen meetings have been held in Jan. & Feb. since the Local Officials Meeting on January 10th.
- Attendees included:
 - > PANYNJ
 - > Turnpike Authority
 - > NJ Transit
 - > Hudson TMA
 - Hudson County
 Improvement Authority
 - Meadowlink
 - > TRANSCOM

- > NYSDOT
- North Jersey Transportation Planning Authority
- Hudson County Engineering
- Kearny Police/Fire
- ➤ Newark Police/Fire
- NJ Motor Truck Association
- Jersey City
 - Engineering
 - Mayor's Office
 - Emergency Management
 - Police
 - Planning



Sample of TMP Mitigation Strategies Advancing

- Addition of third shoulder lane on eastbound NB-HCE (I-78/Turnpike) to Exit 14C (Christopher Columbus Drive)
- Adaptive signal control on Route 1/9 Truck and other key intersections/corridors
- Temporary, full coverage cameras along length of Skyway and at key intersections on diversionary routes
- Provide a coordinated command center for First Responders
- Shuttles/vanpools run from selected locations
- Publicize available Transit options



Sample of TMP Mitigation Strategies Advancing

- During construction, Dynamic Message Signs to provide real time 'travel times' for alternate routes and incident information at select locations in the region using Open Reach system & NJ 511
- Retime signal at Jersey Avenue to favor throughput on I-78/NB-HCE to accommodate volume associated with diverted traffic from Pulaski/Route 139 corridor.
- Construction and alternate route/mode information on NJDOT's website <u>www.pulaskiskyway.com</u>



Continuing Coordination

- Currently, there are eight Subcommittee meetings scheduled for March.
- A new Subcommittee that will include Jersey City,
 Kearny and Hudson County officials is being formed.
- Additionally attendees for Subcommittee meetings are added as identified.
- Additional meetings with local officials and regional agencies are being scheduled.
- Anticipate Jersey City 1 TV adding a voice to the project in the near future.

