

New Jersey Department of Transportation
1035 Parkway Avenue, PO Box 600, Trenton, New Jersey 08625-0600



Baseline Document Change Announcement

ANNOUNCEMENT: BDC24D-02

DATE: September 6, 2024

SUBJECT: Concrete and HMA Sidewalk Width
- Revision to Sheet CD-606-5 of the 2016 Standard Construction Details, Roadway

The 2016 Standard Construction Detail Sheet CD-606-5 is being revised to be consistent with the 2015 Roadway Design Manual, Section 5, Figure 5-B1. The revisions are as follows:

CD-606-5.9 "CONCRETE SIDEWALK, 4" THICK":

- Revise the sidewalk width from "4' - 0"" to "4' MIN. - 5' DES."
- Revise the distance from edge of the sidewalk to the gutter line from "VAR." to "3' MIN. - 6' DES."


CD-606-5.10 "CONCRETE SIDEWALK, 5 1/2" THICK":

- Revise sidewalk width from "VAR." to "4' MIN. - 5' DES."
- Revise the distance from edge of the sidewalk to the gutter line from "VAR." to "3' MIN. - 6' DES."


Implementation Code R (ROUTINE)

Changes must be implemented in all applicable Department projects scheduled for Final Design Submission at least one month after the date of the BDC announcement. This will allow designers to make necessary plan, specifications, and estimate/proposal changes without requiring the need for addenda or postponement of advertisement or receipt of bids.

Recommended By:


Tina Shutz
Director
Capital Program Support

Approved By:


Parth Oza, P.E.
Assistant Commissioner
Capital Program Management
and Deputy State Transportation Engineer